

Blockbuster/Drain Corp Joint Venture Projects.

60m in Bedfordview

A townhouse complex in Bedfordview has had ongoing problems with Santar pipes that are running under the paving. Some small sections had been replaced but a camera inspection revealed that 60m was in need of replacement. This was done over a number of days in 3x 20m stages.



Final Run being prepared

This job involved digging a series of small pits in the paving. We started on the downstream side and worked our way up.



A winch pit

The pipe replacement was completed within a day per run and the actual sewer downtime was about 3 hours.

The Benefits of using BB&DC's pipe replacement method

1. The most cost effective solution – especially if you need to go under buildings, walls, paving and tarred roads.
2. Minimal disruption to the property – we only dig a series of small pits.
3. Little or no contamination of the area we work in – we don't dig up all the contaminated earth and spread it around as you would have to using conventional methods.
4. We can replace the pipe in heavily contaminated ground that is in fact nothing less than a septic tank. The contaminants stay where they are and will ultimately become inert.
5. The replacement is quick and disruption to sewerage flow minimal.
6. Pipe is replaced. You thus have a brand new pipe that is round and smooth inside with no compromised structural integrity.
7. **Immensely strong HDPE (class 6-10) pipe with a minimum of joins will provide hassle free sewerage flow for the next 100 years!**

Contact : Graham Rogers – 083 6252267 or Lee Brand – 083 458 4836

Website at www.blockbusterdrain.co.za